BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2018-19/OW/WORK_INDENT31828

APPROVED SCHEDULE - B

P/BBMP/E-PMT/09/2018-19, Date: 25.09.2018

Improvements of Drains and construction of culverts in Hegadenagara, Thanisandra and Saraipalya surrounding area in ward No. 06 Byatarayanapura Sub Division (2nd Call)

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B Girish ( )	
				In Figures	In Words
1	302.4	KSRRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification.	Cum	180.0	Rupees One Hundred Eighty Only
2	37.8	KSRB 4-1.2: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Sqm	5100.0	Rupees Five Thousand One Hundred Only
3	90.72	KSRB 5.2-3: Providing and constructing granite size stone masonry in foundation cement mortor 1:6, stone hammered dressed in courses not less than 20cms high, bond stones at 2m. apart in each course including cost of materaials, labour, curing complete as per specifications.	Cum	3900.0	Rupees Three Thousand Nine Hundred Only
4	151.2	KSRB 15.1.1 Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	98.0	Rupees Ninety Eight Only
5	15.12	KSRB 4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5400.0	Rupees Five Thousand Four Hundred Only
6	226.8	Providing and fixing RCC Precast cover slab of 250mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	5050.0	Rupees Five Thousand Fifty Only

B. Girish

Signature of the Contractor

18/9

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

18/9